

August 5, 2016 **Chatham County**

Subject: Subdivision Final Plan Review – Cedar Mountain Phase 3A Subdivision off of Cedar Grove Road off SR 1540

Lewis Metty Development, INC. c/o Lewis Metty 565 Oak Hill Road Pittsboro, North Carolina 27313

Dear Mr. Metty:

The N. C. Department of Transportation, Division of Highways has reviewed the construction plans signed and sealed by Samir Bahho P.E. on May 5. 2016 as submitted to this office and approval is granted subject to the following stipulations and recommendations:

- 1. All Construction is to be in accordance with the details as shown on the plans, as well as conform to the most recent edition of the *Standard Specifications for Roads and Structures*.
- 2. A Driveway Permit is not needed for this package.
- 3. The entire proposed right of way is to be cleared and grubbed throughout the whole phase of the project. Please be aware that the areas within the sight distance quadrants are to be treated as right of way.
- 4. All soil areas within the proposed right of way and any other soil areas disturbed during construction shall be seeded and mulched immediately upon completion of roadway construction. The seeding shall be done as outlined in the seeding specification attachment.
- 5. The crossline drainage is approved as proposed on the construction plans. If, however field conditions dictate any changes, these shall be made upon approval by NCDOT. If any of the property owners desire to pipe their ditches within the proposed NCDOT right of way, please advise them that this work should conform to NCDOT specifications for this type of work (see attached). If any ditches are piped and not satisfactorily completed to NCDOT specifications, this could result in the road not being accepted for addition to the state maintained system of roads. Any ditches piped or other encroachment prior to addition to the state maintained system are subject to an encroachment agreement, as are utility companies, when the road is added.



Cedar Mountain Phase 3A Subdivision Final Plan Approval Plans signed and sealed by Samir Bahho P.E. May 5, 2016 Page 2 of 3

- 6. The typicals as shown in the plans, are approved.
- 7. The Division of Highways will only allow mailboxes, with non-rigid type post, such as 4" x 4" wooden or small diameter metal type on new additions. Brick columns or mailboxes on rigid stands such as block, stone or any other type deemed to be a traffic hazard will not be allowed within the right of way. This policy applies to all roads being considered for addition to the State Maintained System.
- 8. An erosion control plan shall require approval from Chatham County. The developer should forward this plan to Mr. Jim Willis, Erosion and Sediment Control Officer, 80 East, P.O. Box 130, Pittsboro, N.C. 27312, phone (919) 545-8343 for his review and approval.
- 9. As this subdivision is proposed to be public and is likely to be requested to be added to the state maintained system of roads, the developer will be responsible for providing a PE Certification, (See Attached) and testing results for base and asphalt density stating that the streets have been built in accordance with the most current "Subdivision Roads: Minimum Construction Standards" manual and with the attached approved plans. Please be advised that this PE Certification does not approve the road for addition to the State Highway System for maintenance. When the proper home density is achieved and roads have been satisfactorily maintained, the developer or property owners must submit Form SR-1, Petition for Road Addition (copy attached to this correspondence), and four (4) copies of the recorded plat to request that the road or roads be added to the State Highway system. Any maintenance problems found when the road is requested to be added must be repaired by the developer prior to the road becoming state maintained. As stated in GS 136-102.6, final acceptance by the Division of Highways of the public streets and placing them on the State highway system for maintenance shall be conclusive proof that the streets have been constructed according to the minimum standards of the Board of Transportation.
- 10. The developer shall comply with all applicable local, state, and federal environmental regulations, and shall obtain all necessary local, state, and federal environmental permits, including, but not limited to, those related to sediment control, stormwater, wetlands, streams, endangered species, and historical sites.
- 11. A properly completed Verification of Compliance with the Department of Environment and Natural Resources (DENR)(page 35, attached) must be submitted prior to the road(s) being considered for addition to the NCDOT System.
- 12. In preparing the final plat for certification by this office and subsequent recording, the following information will be incorporated:
 - A. The sight distance quadrants at the intersections shall be shown either as a public easement or as the property line.
 - B. Public easements for drainage throughout the development.



Cedar Mountain Phase 3A Subdivision Final Plan Approval Plans signed and sealed by Samir Bahho P.E. May 5, 2016 Page 3 of 3

- C. All roads shall be shown as public and the right of way width shown
- D. If the plans of this subdivision change in a way that would cause a change in the classification of these roads from Local Residential to Residential Collector the developer will be responsible for upgrading roads to meet Residential Collector standards prior to addition the state maintenance system.
- E. This approval does not approve the utilities within this subdivision. Any utilities shall be submitted for approval to this office via a properly executed Encroachment Agreement to be approved at the time the roads within the subdivision are petitioned to be added to the state system for maintenance. Please note that water valves should be located a minimum of 6' from edge of pavement, fire hydrants should be behind the right of way line and all service taps should be installed prior to paving.

If you have any further questions regarding this matter, please do not hesitate to call this office at 336. 318.4000

Yours truly,

Docusigned by:

Mark C. J. Muser

Marty C. Tillman District Engineer

-E72EF75317784CB.

Attachments

cc: Brandon Jones, P.E., Division Engineer
Justin Bullock, P.E., Chatham County Maintenance Engineer
Lynn Richardson, Chatham County Planning
Samir Bahho, P.E, Civil and Structural Engineering Services, PLLC.
File





STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION

PAT MCCRORY GOVERNOR DIVISION OF HIGHWAYS

ANTHONY J. TATA SECRETARY

PROFESSIONAL ENGINEER CERTIFICATION SUBDIVISIONS AND COMMERCIAL DRIVEWAYS DIVISION 8, DISTRICT 1


DATE:	_		
COUNTY:	oo.		
SUBDIVISION NAME:			
STREET NAMES	From Sta. No.	To Sta. No.	-
This is to certify that the above lis	ted roads have been co	nstructed in accordance with the ap	proved plans and all
aspects of the most current Subdiv	ision Roads: Minimum	Construction Standards manual.	
1	NAME:		
SIGNA	TURE:		
NC PE LICE	NSE #:		

Professional Engineer Seal

North Carolina Department of Transportation Division of Highways Petition for Road Addition

ROADVAY INFORMATION: (Please Pri	nt/Type)		
County: Road N	Vame: (Please list additional stree	t names and lengths on the b	eack of this form.)
Subdivision Name:		Length (miles):	
Number of occupied homes having stree	et frontage:	Located (miles):	
miles N S E W of the inter	section of Route (SR, NC	and Route	(SR, NC, US)
We, the undersigned, being property ow	ners and/or developers of	A	in
County, do hereby requ	uest the Division of Highw	ays to add the abo	ove described road.
CONTACT PERSON: Name and Address of	First Petitioner. (Please Print/Type)	
Name:	Ph	one Number:	
Street Address:			
Mailing Address:			
	PROPERTY OWNERS		
<u>Name</u>	Mailing Address		<u>Telephone</u>
	**************************************		WARREN STATE OF THE STATE OF TH

 INSTRUCTIONS FOR COMPLETING PETITION: Complete Information Section Identify Contact Person (This person serves as Attach four (4) copies of recorded subdivision Adjoining property owners and/or the developed NCDOT review and approval only require the control of the submitted by the developer, encroachment as way shall be submitted with the petition for Rose required at this time. Submit to District Engineer's Office. 	s spokesperson for p plat or property deed er may submit a petiti developer's signature agreements from all u	s, which refer to con. Subdivision r tilities located wit	roads with prior thin the right of	
FOR NCDOT USE ONLY: Please check the a Rural Road Subdivision platted prior to October		sion platted after Se	eptember 30, 1975	
REQUIREMENTS FOR ADDITION				
If this road meets the requirements necessary Transportation a right-of-way of the necessary construction standards of the NCDOT. The rigis requested to be added to the state maintain of the right-or-way for cut and fill slopes and downway at intersections for sight distance and desforms that will be submitted to us by represent cleared at no expense to the NCDOT, which in obstructions, etc.	width to construct of the will externed system and will rainage. Also, we assign purposes and exatives of the NCDC	the road to the rand the entire lend include the necessigned to dedicate the courte said right. The right-of-	minimum gth of the road that essary areas outsid e additional right-of nt-of-way agreemen -way shall be	e
General Statute 136-102.6 (see page 29 for Statute 1, 1975, must be built in accordance addition to the State Road System.				9
ROAD NAME HOMES LENGTH	ROAD NAME	HOMES	LENGTH	



POSSIBLE SUPPLIERS FOR GRATES AND FRAMES

SOUTHERN FOUNDRY P.O. BOX 186 APEX, N.C. 27502 (919) 362-7744 NORFOLK CAST, INC. P.O. BOX 328 NORFOLK, VA. 23501

VULCAN FOUNDRY CORP. P.O. BOX 905 DENHAM SPRINGS, LA. 1(800)626-4653 US FOUNDRY 8351 N. W.93RD ST MEDLEY, FLA.33166 (305)885-0301 FAX (305) 844-3253

SUPER CAST, INC. 1104 US HWY, 117 BYPASS, S. GOLDSBORO, N.C. 27530 (919)736-9010 FAX (919)736-0290

BUNCH PATTERN WORKS, INC. P.O. BOX 267 HWY 308 N. LEWISTON-WOODVILLE,N.C. 27849

CAPITAL FOUNDRY OF VIRGINIA, INC. P.O. BOX 2212 VIRGINIA BEACH, VIRGINIA 23450

EMPORIA FOUNDRY, INC. 620 REESE STREET EMPORIA, VIRGINIA 23847

ENNIS ENTERPRISES P.O. BOX 931 WILMINGTON, N.C. 28402 (910) 371-9323

15, INUN 30, bibE JETWI AONG NOINE

1-121 \$TATE OF NORTH CAROLINA DEPT. OF TRANSPORTATION OF HIGHWAYS PAREIGH, N.C.

USE BRICK OF CONCRETE BLOCK WHICH COMPLIES WITH THE REQUIREMENTS OF WESTION SAD OF THE STANDARD SPECIFICANS.

CANSTRICT WITH FIFE CROSMS BATCHINE.

CHAMMEN ALL EXPERS ASPRERS 1"

DRAWING NOT TO SCALE.

SBTAK NAPTHA (THETTEWTAL) - III EFEGLION -

11 %

PROVIDE ALL CATCH BASINS OVER S'-0" IN DEPTH WITH STEPS 12" ON CENTER, USE STEES WHICH COUPLY WITH STD, DRAWING S40.AB.

DEDLAT FOR FIFE; S! FROM TOTAL OU. YOS. OF BHICK MASCURY.

THE FORMS FOR STRATFORCY OF THE BOTTOM RIAS.


INF & BAR CLAFF & AT 17" OFFITHE

MONTAL JOINTS 14" +1- 14" THICK. USE CLASS "R" CONCASTE THROUGHOUT.


GENERAL MOTES:

ROS SMIMARO ORACNATZ HZIJONS

IT REINFORCED CONDRETE PIPE IS SET IN BOTTON SLAB OF BOX, ADD TO SLAB AS SHOWN ON STO. ND. 840.00.
FOR 5.0" IN HIGH- OR LESS, LEE, B. WALL, OVER 8.0. IN HIGH-T, LBC
18" WALL TO 8-0" FROM TOR DF WALL AND 8" WALL FOR THE REMAINING
6"-0". QLANTITES TO BE ADJUSTED ACCORDINGLY. SEE STANDARD DAAMING 84D. 25 FOR ATTACHMENT OF FRAMES AND GRATES 44 BAB DO NOT USE BAICK MASOMRY DROP INFET IN LOCATIONS SUBJECT TO TRAFFIC.








	 And the second s	
		MA. PIPE IN.S SUB-
H	OCCUPANO.	940

SECTION

PIPE

HHHHHH

pointers	ymrone	elbiciery.	granicolistanuota	gyermon	gavaicuci	STATE OF THE	ÇE KOORTIO	orzas
, es.,	DAS FOR		ú	0.022	0.047	0.086	0.118	0.170
MEIGHT, N	DEDUCTIONS	P.F.	# ပ်	0.090	0.381	0,64	0.478	0.122
MEN.	CUBIC WARRS	MASONTY	FER TETAL ENICK SASSET FOR	4. GSSD .	9.600	0.678	10 10 10 10 10	198-0
THLET (ELEED ON	CUBIT	BAICK	MAII PER FOOT HT.	0.03	0.913	80 80 80 80	% 50 50	Q.918
es for each	CUBIC YARDS	COMERETE	20172W	ර . පරිම ම	C.1468	0.284	18 19 C	2.0 888
and Cuanteties	SIOVS OF BOX & PIPE	MIN. HEIGHT	æ	71.D"	On Pu	7. .e.		
pinengidas and	OF BOX	WIDTH (eD:	 	**pt	Market Comment	100	e e
CIPE	81 DVS	Pak	Æ,	. D.	Silve	No.		,0.




ENGLISH STANDARD DRAWING FOR BRICK DROP INLET 12" THRU 30" PIPE

STATE OF U-12 NORTH CAROLINA EPT. OF TRANSPORTATION DIVISION OF HIGHWAYS RAIFTCH N.C. 1 - 12

340.16

FOR USE NITH \$10. DWG.S 840.14 AND 840.15 INTEL ENVIR VND GRATES dOMO

DIVISION OF HIGHWAYS .C. DEPT, OF TRANSPORTATION ENGLISH STANDARD DRAWING FOR



11-12STATE OF U-12
NORTH CAROLINA
DEPT. OF TRANSPORTATION DIVISION OF HIGHWAYS

RIATE OF

DROP INLET FRAME AND GRATES FOR USE WITH STD. DWG.S 840.14 AND 840.15

ENGLISH STANDARD DRAWING FOR

VERIFICATION OF COMPLIANCE WITH ENVIRONMENTAL REGULATIONS

(Clieck Appropriate Box)

Permits from the N.C. Department of U.S. Army Corp of Engineers are napplicable federal and state regulations by	ot required for this p	ral Resources and the roject. However, all
The required permits from the N.C. Resources and the U.S. Army Corp of I Copies of permits and Completion Certif	Engineers have been ob	ronment and Natural tained for this project.
All applicable NPDES Stormwater Perm (The applicant should contact the N.C determine if a stormwater permit is requi	 Division of Water 	en met for this project. Quality in Raleigh to
The project is in compliance with all app laws and regulations.	dicable sedimentation a	nd erosion control
Project Name:	pomora kirjano kirjano 145.	
Township:	CHILTY	
Project Engineer:	Phone No.:	
Project Contact:	Matheura are now a story prop	
Applicants Name:	and the state of t	P.E. SEAL
Date Submitted:	n normal name in the section of the	
(Reference Page 11, Item 10)		11/07/2003

ATTACHMENT "A"

Seeding and mulching shall be in accordance with Section 080 of the North Carolina Standard Specifications for Roads and Structures, except that Articles 680-8(8) shall not apply. Final determination of soil type shall be made by the Engineer. The following rates in pounds per acre shall apply:

SANDY SOLL

CLAY SOLL

Alta Tall Fescue

50# - KY 31 Tall Feacue or 100# - KY 31 Tall Feacue or Alta Tall Fescue

5# - Centipede

15# - Kenblue Bluegrass

50# - Pensacola Babiagrasa

500# - Fertllizer

500# - Fertilizer

4000% - Limestone


4000# - Limestone

Add 18# Kobe or Korean Lespedeza and 10# Millet to the above mixture from May 1 to August 31.

On cut and fill slopes 2:1 or steeper, add 30% Serices Lespedeza from Asnuary I to December 31.

Fertilizer shall be 10-20-20 analysis. Upon written approval of the Engineer, a different analysis of fertilizer may be used provided the 1-2-2 ratio is maintained and the rate of application adjusted to provide the same amount of plant food as a 10-20-20 analysis.

CEDAR MOUNTAIN SUBDIVISION PHASE 3A



NOTES

- 1. ALL PIPE DEPTH COVER AND MATERIAL SHALL BE IN ACCORDANCE WITH THE NCDOT PIPE MATERIAL SELECTION GUIDE.
- 2. ALL DITCHES MUST BE STABLE PRIOR TO ACCEPTANCE BY NCDOT.

CONSTRUCTION SEQUENCE

- 1. BEFORE ANY CLEARING AND GRADING CONSTRUCTION ON THE SITE BEGINS, CONTRACTOR SHALL CALL FOR A PRECONSTRUCTION CONFERENCE TO INCLUDE CHATHAM COUNTY REPRESENTATIVE, CONTRACTOR, OWNER AND PROJECT ENGINEER. PRECONSTRUCTION CONFERENCE SERVES TO EXCHANGE INFORMATION ABOUT CONTACT PERSONS INVOLVED IN THE CONSTRUCTION OF SITE IN ORDER TO ESTABLISH THE RIGHT WAY OF COMMUNICATION AND KNOW THE PROCEDURES TO BE FOLLOWED DURING CONSTRUCTION. CONTRACTOR SHALL START BY CONSTRUCTION EROSION AND SEDIMENT CONTROL DEVICES AS FOLLOWS:
- CLEAR ENOUGH AREAS OF ROADS TO THE INSTALLATION E&SC DEVICES.
- INSTALL CONSTRUCTION ENTRANCE AS SHOWN ON E&SC PLAN AND DETAILS
- INSTALL SILT FENCE/TREE PROTECTION FENCE AS SHOWN ON E&SC PLAN AND DETAILS
- SEDIMENT PITS AS SHOWN ON CONSTRUCTION DRAWINGS
- 2. REMOVE TOP SOIL AND STORE IT IN THE DESIGNATED AREA "STOCK PILE". SOIL SHALL BE AERATED AND LATER USED AS TOP SOIL IN VEGETATED AREAS OR DISPOSED OF IT AND SEEDED PROPERLY. TOP SOIL TO BE REMOVED AS GRADING OPERATIONS IN 3, 4, 5, AND 6.

3. GRADING OPERATIONS TO STATION 85+00

- INSTALL CROSS PIPE #1 AND ALL THE E&SC MEASURES AROUND THE PIPE AS SHOWN ON CONSTRUCTION PLAN.
- CONTINUE GRADING AND INSTALLING TEMPORARY DRAINAGE DITCHES AND CHECK DAM AS GRADING PROGRESSES TO STATION 85+00
- PROTECT CROSS DITCH AT PIPE #3 BY A CROSS THE ROAD SILT FENCE TO DIVERT CONSTRUCTION DRAIN WATER TO SEDIMENT PIT #1 AND #2 UNTIL CONSTRUCTION IS READY TO PROGRESS PAST STATION 85+00
- ADJUST SILT FENCES, TEMPORARY DITCHES AND ROCK DAMS WITH CHANGES IN EXCAVATION AND GRADING ELEVATIONS.

4. GRADING OPERATION TO STATION 90+00

- BEFORE PROGRESS IN GRADING OPERATIONS PAST STATION 85+00:
- INSTALL CROSS PIPE #3 AND ALL THE E&SC MEASURES AROUND THE PIPE AS SHOWN ON CONSTRUCTION PLAN
- CONTINUE GRADING AND INSTALLING TEMPORARY DRAINAGE DITCHES AND CHECK DAM AS GRADING PROGRESSES TO STATION 90+00
- PROTECT CROSS DITCH AT PIPE #4 BY INSTALLING CROSS THE ROAD SILT FENCE TO DIVERT CONSTRUCTION DRAIN WATER TO SILT FENCE OUTLET DEVICES LEFT AND RIGHT UNTIL CONSTRUCTION IS READY TO PROGRESS PAST STATION 90+00
- ADJUST SILT FENCES, TEMPORARY DITCHES AND ROCK DAMS WITH CHANGES IN EXCAVATION AND GRADING ELEVATIONS CONSTRUCTION DRAIN
- 5. GRADING FROM STATION 90+00 TO END OF ROAD BEFORE PROGRESSING WITH GRADING OPERATIONS PAST STATION 90+00:
- INSTALL CROSS PIPE #4 AND ALL THE E&SC MEASURES AROUND THE PIPE AS SHOWN ON CONSTRUCTION PLAN
- CONTINUE GRADING AND INSTALLING TEMPORARY DRAINAGE DITCHES AND CHECK DAMS AS GRADING PROGRESSES TO THE END STATION OF CEDAR GROVE ROAD AS SHOWN
 ON CONSTRUCTION BLANCE.
- ADJUST SILT FENCES, TEMPORARY DITCHES AND ROCK DAMS WITH CHANGES IN EXCAVATION AND GRADING ELEVATIONS CONSTRUCTION DRAIN

6. EAGLE CREST COURT:

- CONTINUE GRADING AND INSTALLING TEMPORARY DRAINAGE DITCHES AND CHECK DAM AS GRADING PROGRESSES TO STATION TO THE END OF CUL-DE-SAC
- ADJUST SILT FENCES, TEMPORARY DITCHES AND ROCK DAMS WITH CHANGES IN EXCAVATION AND GRADING ELEVATIONS.

7. OWLS NEST COURT:

- INSTALL CROSS PIPE #2 AND ALL THE E&SC MEASURES AROUND THE PIPE AS SHOWN ON CONSTRUCTION PLAN
- CONTINUE GRADING AND INSTALLING TEMPORARY DRAINAGE DITCHES AND CHECK DAM AS GRADING PROGRESSES TO THE END OF CUL-DE-SAC

 TOTAL CONTINUE GRADING AND INSTALLING TEMPORARY DRAINAGE DITCHES AND CHECK DAM AS GRADING PROGRESSES TO THE END OF CUL-DE-SAC

 TOTAL CONTINUE GRADING AND INSTALLING TEMPORARY DRAINAGE DITCHES AND CHECK DAM AS GRADING PROGRESSES TO THE END OF CUL-DE-SAC


 TOTAL CONTINUE GRADING AND INSTALLING TEMPORARY DRAINAGE DITCHES AND CHECK DAM AS GRADING PROGRESSES TO THE END OF CUL-DE-SAC

 TOTAL CONTINUE GRADING AND INSTALLING TEMPORARY DRAINAGE DITCHES AND CHECK DAM AS GRADING PROGRESSES TO THE END OF CUL-DE-SAC

 TOTAL CONTINUE GRADING AND INSTALLING TEMPORARY DRAINAGE DITCHES AND CHECK DAM AS GRADING PROGRESSES TO THE END OF CUL-DE-SAC

 TOTAL CONTINUE GRADING TEMPORARY DRAINAGE DITCHES AND CHECK DAM AS GRADING PROGRESSES TO THE END OF CUL-DE-SAC

 TOTAL CONTINUE GRADING TEMPORARY DRAINAGE DITCHES AND CHECK DAM AS GRADING TEMPORARY DRAINAGE DAM AS GRADING TEMPORARY DRAINA
- ADJUST SILT FENCES, TEMPORARY DITCHES AND ROCK DAMS WITH CHANGES IN EXCAVATION AND GRADING ELEVATIONS.



DRAINAGE AREAS FOR CROSS PIPES

EROSION AND SEDIMENT CONTROL CONSTRUCTION AND MAINTENANCE NOTES

- 1. THE CONTRACTOR SHALL DESIGNATE AN EROSION AND SEDIMENT CONTROL COORDINATOR FOR THE SITE
- 2. HOLD PRE-CONSTRUCTION MEETING AT LEAST ONE WEEK BEFORE THE START OF ANY CONSTRUCTION OPERATION. INVITE TOWN OF CHATHAM COUNTY EROSION AND SEDIMENT CONTROL COORDINATOR.
- 3. CLEAR ENOUGH AREA TO START INSTALLING E&SC DEVICES AS PER DETAILS SHOWN ON THE EROSION AND SEDIMENT CONTROL PLANS AND DETAIL SHEETS
- 4. START CLEARING AND GRUBBING OPERATIONS. INSTALL CROSS DRAINAGE PIPES AS THE CLEARING AND GRUBBING OPERATIONS PROGRESS AND REACH DRAINAGE CROSS PIPES AS SHOWN ON CONSTRUCTION PLANS. INSTALL E&SC MEASURES AROUND THE INSTALLED CROSS PIPES AS SHOWN ON THE CONSTRUCTION PLANS.
- 5. START CONSTRUCTION OPERATIONS AS OUTLINED ON THE PROJECT PLANS
- 6. ADJUST E&SC DEVICES AS OUTLINED IN THE CONSTRUCTION SEQUENCE IN ORDER TO PERFORM PROPERLY WITH THE NEW GRADE
- 7. WHEN CHANGES IN CONSTRUCTION ACTIVITIES SEQUENCE ARE NEEDED, AMEND E&SC PRACTICES TO MAINTAIN MANAGEMENT CONTROL. CONSULT WITH THE PROJECT ENGINEER BEFORE MAKING CHANGES.
- 8. ALL GRADED AREAS WILL BE SEEDED, FERTILIZED AND MULCHED TO MAINTAIN A VIGOROUS, DENSE VEGETATIVE COVER WITHIN 7 DAYS OR 14 CALENDAR DAYS (WHICHEVER IS SHORTER) OF COMPLETION OF ANY PHASE OF GRADING. IF WORK ON THE PROJECT CEASES FOR MORE THAN THE AFOREMENTIONED LENGTH OF TIME, ALL DISTURBED AREAS SHALL HAVE TEMPORARY VEGETATIVE GROUND COVER ESTABLISHED AND EROSION CONTROL PRACTICES MAINTAINED.
- 9. ALL EROSION AND SEDIMENT CONTROL PRACTICES SHALL BE INSPECTED WEEKLY AND AFTER RAINFALL EVENTS. NEEDED REPAIR SHALL BE MADE IMMEDIATELY.
- 10. ESTIMATED TIME BEFORE FINAL STABILIZATION IS 6 MONTHS
- 11. ESTIMATED DISTURBED AREA IS APPROXIMATELY 6 ACRES
- 12. AFTER SITE IS STABILIZED, TEMPORARY SEDIMENT TRAPS, TEMPORARY DIVERSIONS, CONSTRUCTION ENTRANCE AND CONSTRUCTION STAGING AND MATERIAL STOCKPILE AREAS AND OTHER EROSION CONTROL DEVICES SHALL BE REMOVED, RESTORED TO ORIGINAL AND PERMANENTLY VEGETATED. CONTRACTOR SHALL RECEIVE PERMISSION FROM THE PROJECT INSPECTOR BEFORE REMOVING AND E&SC DEVICES.
- 13. CONTRACTOR IS RESPONSIBLE FOR INSTALLATION, MAINTENANCE AND REMOVAL OF ALL TEMPORARY E&SC DEVICES ON THE PROJECT.
- 14. AREA TO BE PERMANENTLY STABILIZED WITH VEGETATION IS APPROXIMATELY 3 ACRES

MAINTENANCE OF EROSION AND SEDIMENT CONTROL PRACTICES

- 1. THE CONTRACTOR SHALL CHECK ALL EROSION AND SEDIMENT CONTROL PRACTICES FOR STABILITY AND OPERATION FOLLOWING EVERY RUNOFF PRODUCING RAINFALL BUT IN NO CASE LESS THAN ONCE EVERY WEEK. ANY NEEDED REPAIRS WILL BE MADE IMMEDIATELY BY THE CONTRACTOR TO MAINTAIN ALL PRACTICES AS DESIGNED. ALSO PER NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM (NPDES), A RAIN GAUGE MUST BE INSTALLED ON SITE. THE RAIN GAUGE MUST BE KEPT ONSITE AND INSPECTED BY THE CONTRACTOR MUST BE MADE AND LOGGED AFTER EVERY HALF INCH RAINFALL OR ONCE A WEEK.
- 2. THE CONTACTOR SHALL REMOVE SEDIMENT FROM SEDIMENT BASINS/TRAPS WHEN STORAGE CAPACITY HAS BEEN APPROXIMATELY 50% FILLED OF FIRST BAFFLE. GRAVEL SHALL BE CLEANED OR REPLACED WHEN THE SEDIMENT POOL NO LONGER DRAINS PROPERLY. REPAIR BAFFLES IF DAMAGED AND REMOVE DEBRIS FROM SKIMMER.
- 3. THE CONTRACTOR SHALL REMOVE SEDIMENT FROM BEHIND SILT FENCE WHEN IT BECOMES (0.5') DEEP AT THE FENCE. SILT FENCE SHALL BE REPAIRED AS NECESSARY TO MAINTAIN A BARRIER. CONTRACTOR SHALL RESTORE SEDIMENT STORAGE AREA FOR PIPE INLET PROTECTION TO ITS ORIGINAL DIMENSIONS WHEN SEDIMENT HAS ACCUMULATED TO 1/2 DESIGN DEPTH. CONTRACTOR SHALL REPAIR ANY DAMAGE TO THE STRUCTURE OF INLET DISPLACED STONE AND RIP RAP
- 4. THE CONTRACTOR SHALL FERTILIZE, RESEED AS NECESSARY, AND MULCH ALL SEEDED AREAS ACCORDING TO SEEDING SPECIFICATION IN THE PLANS TO MAINTAIN VIGOROUS, DENSE VEGETATIVE COVER.
- 5. THE CONTRACTOR SHALL PROVIDE GROUND COVER ON EXPOSED SLOPES OR OTHER AREAS WITHIN 21 CALENDAR DAYS OF COMPLETION OF ANY PHASE OF GRADING. PERMANENT GROUND COVER IS TO BE PROVIDED FOR ALL DISTURBED AREA WITHIN 21 CALENDAR DAYS OR SOONER AFTER COMPLETION OF CONSTRUCTION OR DEVELOPMENT.
- 6. THE EROSION & SEDIMENT CONTROL DESIGNATED COORDINATOR SHALL FAMILIARIZE HIM/HERSELF WITH MAINTENANCE PROCEDURES IN THE PRACTICE STANDARDS AND SPECIFICATIONS (EROSION AND SEDIMENT CONTROL PLANNING AND DESIGN MANUAL) AND MAKE RECOMMENDATIONS.

DEVELOPER/OWNER: LEWIS METTY DEVELOPMENT, INC ADDRESS: 565 OAK HILL ROAD PITTSBORO, NC 27313

CONTACT PERSON: CHARLES E. LEWIS TELEPHONE: 919-619-9878 EMAIL ADDRESS: LEWISBLDGCO@BELLSOUTH.NET

ENGINEERS: CIVIL AND STRUCTU


CIVIL AND STRUCTURAL ENGINEERNG SERVICES, PLLC CONTACT PERSON: SAMIR BAHHO, PE TELEPHONE: 919-851-1642 EMAIL ADDRESS: BA.CASESPLLC@GMAIL.COM

SURVEYORS: MAERSTAN, PLLC ADDRESS: 140 IOWA LANE, SUITE 104 CARY, NC 27511 CONTACT PERSON: RICHARD BULLOCK, PLS

EMAIL ADDRESS: RICHARD@MAERSTAN.COM

SHEET INDEX

1 OVERALL PROJECT AND DRAINAGE AREAS
2 CEDAR GROVE ROAD STATION 69+00 - 81+00
3 CEDAR GROVE ROAD STATION 81+00 - 95+00
4 EAGLES CREST COURT STATION 9+50 - 15+59
5 OWLS NEST COURT STATION 10+00 - 18+36
6 CONSTRUCTION DETAILS



CEDAR MOUNTAIN SUBDIVISION PHASE IV OUTLINES

SAMIR W. BAHHO, PE & STRUCTURAL ENGINEERING SE 4612 KAPLAN DRIVE RALEIGH NORTH CAROLINA 27606

NN PHASE 3A
NORTH CAROLINA
FENT CONTROL PLAN

MOUNTAIN SUBDIV

CEDAK M

BALDWIN TOWNSHIP

ROADWAY COI

DATE DESCRIPTION
2/22/16 RESPONSE TO CHATHAM COUNTY REVIEW COMMENTS
4/20/16 RESPONSE TO NC DOT REVIEW COMMENTS

DATE:
01.09.16

SCALE:
AS NOTED

DESIGNED:
SWB

DRAWN:
SWH


APPROVED:
LMDC LLC


SHEET:


1 OF 6

CAD FILE:
CEDAR
PROJECT NO:

PROJECT NO: 2015.C








EAGLES CREST


CEDAR MOUNTAIN SUBDIVISION PHASE IN TOWNSHIP
ROADWAY


4 _{of} 6

CAD FILE: CEDAR PROJECT NO: 2015.01

W. BAHHO, ENGINEERING









NEW LOCAL RESIDENTIAL ROAD OR COLLECTOR ROAD
AND EXISTING STATE MAINTAINED ROAD
WITHOUT CURB AND GUTTER

STOP CONDITION





1. PLACE STONE TO THE LINES AND DIMENSIONS SHOWN ON THE PLAN ON A FILTER FABRIC FOUNDATION.

2. KEEP THE CENTER STONE SECTION AT LEAST 9 INCHES BELOW NATURAL GROUND WHERE THE DAM ABUTS THE CHANNEL BANKS.


3. EXTEND STONE AT LEAST 1.5 FEET BEYOND THE DITCH BANK TO KEEP WATER FROM CUTTING AROUND THE ENDS OF THE CHECK DAM.

4. SET SPACING BETWEEN DAMS TO ASSURE THAT THE ELEVATION AT THE TOP OF THE LOWER DAM IS THE SAME AS THE ELEVATION OF THE TOE OF THE UPPER DAM.

5. PROTECT THE CHANNEL AFTER THE LOWEST CHECK DAM FROM HEAVY FLOW THAT COULD CAUSE EROSION.

6. MAKE SURE THAT THE CHANNEL REACH ABOVE THE MOST UPSTREAM DAM IS

7. ENSURE THAT OTHER AREAS OF THE CHANNEL, SUCH AS CULVERT ENTRANCES BELOW THE CHECKS DAMS, ARE NOT SUBJECT TO BLOCKAGE FROM DISPLACED STONES.



SOIL AMENDMENTS

FOLLOW RECOMMENDATIONS OF SOIL TESTS OR APPLY 2,000 LB/ACRE GROUND AGRICULUTURAL LIMESTONE.

APPLY 4,000 LB/ACRE STRAW. ANCHOR STRAW BY TACKING WITH ASPHALT, NETTING OR A MULCH ANCHORING TOOL. A DISK WITH BLADES SET NEARLY STRAIGHT CAN BE USED AS A MULCH ANCHORING TOOL.

MAINTENANCE

* RE-FERTILIZE IF GROWTH IS NOT FULLY ADEQUATE. RE-SEED, RE-FERTILIZE AND MULCH IMMEDIATELY FOLLOWING EROSION OR OTHER DAMAGE.

** REPAIR AND RE-FERTILIZE DAMAGED AREAS IMMEDIATELY. TOP-DRESS WITH 50 LB/ACRE OF NITROGEN IN MARCH. IF IT IS NECESSARY TO EXTEND TEMPORARY COVER BEYOND JUNE 15, OVER SEED WITH 50 LB/ACRE OF KOBE IN LATE FEBRUARY OF EARLY MARCH.


D:\Projects\Cedar Mountain\provided info\EC DETAIL.jpg


PERMANENT SEEDING SCHEDULE


SHOULDERS, SIDE	E DITCHES, SLOPES (MAX. 3:1)	
SEEDING DATES	SPECIES	RATE
AUGUST 15-NOV 1 NOV 1-MARCH 1 NOV 1-MARCH 1 MARCH 1-APRIL 15 APRIL 15-JUNE 30 JULY 1-AUGUST 15 JULY 1-AUGUST 15	HULLED COMMON BERMUDAGRASS	300 LB/ACRE 50 LB/ACRE 50 LB/ACRE 300 LB/ACRE 25 LB/ACRE 120 LB/ACRE 35 LB/ACRE
SHOULDERS, SIDE	E DITCHES, SLOPES (3:1 TO 2:1)
SEEDING DATES	SPECIES	RATE
MARCH 1-JUNE 1 MARCH 1-APRIL 15 MARCH 1-JUNE 30	SERICEA LESPEDEZA AND SCARIFY AND ADD TALL FESCUE OR ADD WEEPING LOVE GRASS	50 LB/ACRE 120 LB/ACRE 10 LB/ACRE
JUNE 1-SEPT 1 JUNE 1-SEPT 1	TALL FESCUE AND BROWN TOP MILLET	120 LB/ACRE 35 LB/ACRE
SEPT 1-MARCH 1 SEPT 1-MARCH 1 NOV 1-MARCH 1	SERICEA LESPEDEZA AND TALL FESCUE ADD ABRUZZIE RYE	70 LB/ACRE 120 LB/ACRE 25 LB/ACRE


TEMPORARY SEEDING SCHEDULE

SEEDING DATES	SPECIES	RATE	FERTILZER	
JAN 1-MAY 1	RYE *	120 LB/ACRE	750 LB/ACRE 10-10-10	
MAY 1—AUGUST 15	ANNUAL LESPEDEZA (KOBE) * GERMAN MILLET *	50 LB/ACRE 40 LB/ACRE	750 LB/ACRE 10-10-10 750 LB/ACRE 10-10-10	
AUGUST 15-DEC 31	RYE (GRAIN) **	120 LB/ACRE	1,000 LB/ACRE 10-10-10	
OMIT ANNUAL LESPEDEZA WHEN DURATION OF TEMPORARY COVER IS NOT TO EXTEND BEYOND JUNE.				









TOP OF BAFFLE SHOULD BE 6 HIGHER THAN THE BOTTOM OF THE SPILLWAY THE SPILLWAY BOTTOM OF BAFFLE IN BRENCH AND TRENCH FILLED WITH SOIL AND COMPACTED

NOTES:

1. DRIVE STEEL FENCE POST AT LEAST 18" INTO SOLID GROUND


2. WOOD POSTS ARE NOT ACCEPTABLE


3. USE STAPLES 1' APART TO ATTACH FABRIC TO "HOG WIRE"

4. BAFFLE SPACED AS PER APPROVED PLAN.


BAFFLE INSTALLATION - STEP 2


GRAVEL AND RIP-RAP SEDIMENT TRAP





TYPICAL JUTE MESH LINED DITCH





DESIGNED:
SWB
DRAWN:
S

O1.09.16 1"=

ESIGNED: CHECKED
SWB SV

RAWN: APPROVE
LMDC

CHEET:

OF

CAD FILE:
CEDAR

PROJECT NO: