



CITY OF WASILLA

290 E. HERNING AVE.
WASILLA, ALASKA 99654-7091

Area Code (907)

Administration
Ph: 373-9055
Fx: 373-9085

Clerks Office
Ph: 373-9065
Fx: 373-9085

Finance
Ph: 373-9070
Fx: 373-9085

Library
Ph: 376-5913
Fx: 376-2347

Museum
Ph: 373-9071
Fx: 373-9072

Planning
Ph: 373-9074
Fx: 373-9085

Ph: 373-9077
Fx: 373-9051

Public Works
Ph: 373-9095
Fx: 373-9085

Ph: _____
Fx: _____

COUNCIL MEMORANDUM NO. 95-73

From: Deputy Administrator
Date: September 6, 1995
Subject: **BID AWARD - SEPTIC TANK PURCHASE, CARRS WASTEWATER IMPROVEMENT PROJECT**

As construction time is of the essence; and, there are only two septic tank vendors/fabricators in Alaska, the City has solicited and received bid proposals/quotations for supplying two (2) - 6,000 gallon septic tanks for installation as part of the Carrs Wastewater Improvement Project.

We received two (2) bids/quotations, ranging from a low of \$7,200 each (\$14,400 total) to a high of \$7,800 each (\$15,600 total).

Recommendation: Council approval for Administration to proceed with awarding a contract to the apparent low bidder, Anchorage Tank & Welding, Inc. at the low bid package price of \$14,400.

Lee A. Wyatt
Deputy Administrator

APPROVED

DATE: 9/11/95

BY: [Signature]

17 August, 1995

Request for Material Bids

Bids are invited for furnishing and delivering two 6000-gallon *effective capacity* single compartment steel septic tanks.

Tanks will be cylindrical, approximate dimensions 8-foot diameter by 20-feet long. Effective capacity is defined as the liquid volume contained in a liquid depth of 6-feet. Intent is to provide a septic tank system (tanks will be installed in series) which meets all ADEC requirements and which is structurally sound and which is adequately coated for corrosion protection.

Tank steel plate, 0.25-inch, ASTM A36.

Baffles and rings 12 gauge steel.

Welds AWS D1.1.

Coating, coal tar base or equal, inside and out, 20 mil or as approved.

6-inch inlets and outlets, with baffles inside.

Inlets and outlets maintain 6-foot liquid level.

20-inch manholes on each end of each tank.

Each manhole stands 4-feet above tank to flange.

Each manhole flange watertight.

Manhole flange covers do not exceed 22 inches diameter.

Provide lifting rings or fixtures.

Submit price for two tanks, fob Carrs receiving area, Swanson Avenue, Wasilla. The City is separately hiring a contractor to install the tanks between September 25 and October 6. If tank supplier will hold tanks and coordinate delivery with the City's contractor, the contractor will have equipment to off load the tanks. Otherwise include off loading in bid.

Bids are requested by 5:00 PM on Wednesday, August 23, 1995. Fax bids are acceptable. Order will be placed with the successful bidder on Tuesday, August 29, 1995.

For the City of Wasilla:

Q U O T A T I O N

ANCHORAGE TANK & WELDING, INC.
2700 PORCUPINE DRIVE
ANCHORAGE, ALASKA 99501
272-3543

DATE: 8/28/95

QUOTATION #: Q00997

PHONE #:

CITY OF WASILLA, DEPT OF PUBLIC WORKS
290 HERNING STREET
WASILLA, AK 99687
373-9085

99687

RE: 6,000 GALLON SEPTIC TANKS

QUANTITY	DESCRIPTION	PRICE	TOTAL
2	8000 GALLON SINGLE COMP SEPTIC TANKS PER SPECIFICATION.	7,200.00	14,400.00
			\$14,400.00

F.O.B. WASILLA

TERMS: NET 30

DELIVERY: 4-5 WEEKS

THANK YOU FOR THE OPPORTUNITY TO QUOTE THE ABOVE ITEMS ON YOUR PROJECT.

ANCHORAGE TANK & WELDING, INC.

Louise

277 3715 IS FAX #

RECEIVED

AUG 28 1995

City of Wasilla, Alaska

17 August, 1995

Request for Material Bids

Bids are invited for furnishing and delivering two 6000-gallon *effective capacity* single compartment steel septic tanks.

Tanks will be cylindrical, approximate dimensions 8-foot diameter by 20-foot long. Effective capacity is defined as the liquid volume contained in a liquid depth of 6-feet. Intent is to provide a septic tank system (tanks will be installed in series) which meets all ADEC requirements and which is structurally sound and which is adequately coated for corrosion protection.

Tank steel plate, 0.25-inch, ASTM A36.

Baffles and rings 12 gauge steel.

Welds AWS D1.1.

Coating, ~~and two coats on exterior, inside and out, 70 mil or as specified~~

6-inch inlets and outlets, with baffles inside.

Inlets and outlets maintain 6-foot liquid level.

20-inch manholes on each end of each tank.

Each manhole stands 4-feet above tank to flange.

Each manhole flange watertight.

Manhole flange covers do not exceed 22 inches diameter.

Provide lifting rings or fixtures.

24"

Submit price for two tanks, fob Carrs receiving area, Swanson Avenue, Wasilla. The City is separately hiring a contractor to install the tanks between September 25 and October 6. If tank supplier will hold tanks and coordinate delivery with the City's contractor, the contractor will have equipment to off load the tanks. Otherwise include off loading in bid.

Bids are requested by 5:00 PM on Wednesday, August 23, 1995. Fax bids are acceptable. Order will be placed with the successful bidder on Tuesday, August 29, 1995.

For the City of Wasilla:

\$7800⁰⁰ each

Post-It® Fax Note	7671	Date	8/28	# of pages	1
To	Green Tank	From	City of Wasilla		
Co./Dept	Stephen	Co.			
Phone #	248-2455	Phone #	373-9055		
Fax #	248-9212	Fax #	373-9085		



CITY OF WASILLA

290 E. HERNING AVE.
WASILLA, ALASKA 99654-7091

Area Code (907)

Administration
Ph: 373-9055
Fx: 373-9085

Clerks Office
Ph: 373-9065
Fx: 373-9085

Finance
Ph: 373-9070
Fx: 373-9085

Library
Ph: 376-5913
Fx: 376-2347

Museum
Ph: 373-9071
Fx: 373-9072

Planning
Ph: 373-9074
Fx: 373-9085

Police
Ph: 373-9077
Fx: 373-9051

Public Works
Ph: 373-9095
Fx: 373-9085

Ph: _____
Fx: _____

September 1, 1995

Anchorage Tank

Attention: Lowell

This is notice that the City of Wasilla is accepting your quote to furnish and deliver two 6,000 gallon steel tanks at \$7,200 each. Reference Purchase Order No. 4770 in future correspondence.

I have been advised that you have a computer program which verifies the structural integrity of those tanks. The tanks will be buried under 6 to 8 feet of cover under a loading dock parking area at a grocery store. A 6-inch thick reinforced concrete slab is covering the tanks to distribute traffic loads and to prevent floatation. If stiffeners will be needed in the tanks to protect structural integrity, please let me know.

This order is contingent upon your supplying the tanks within the time deadline listed in the RFP.

Please call if you have any questions.

Sincerely,

Lee A. Wyatt
Deputy Administrator

